(21)

BRUHAT BANGALORE MAHANAGARA PALIKE

(Office of the Horticulture Superintendent (South) 2nd Block Jayanagara, Bangalore-560 011)

COMPARTIVE STATEMENT

Sub: Providing and fixing Multi Speciality Play Equipments in Lakshman Rao Boulevard 'C' Park in Yediyur Ward No. 167.

No. :HS(S)/PR/Quotation/Yediyur/10-11, 22.12.2010

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
1	Providing, fabricating and fixing Special Multiplay Systems consists of FRP moulded with Aluminium chequered Platforms of size 5'x5 ft with 4 Support piller made out of 75 mm dia G.I. "B" Pipes fixed in cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be with tubular Slide & Mini Aquva tunnel slide made up of high quality FRP the slide is to fixed at a height of 11 ft and runs runs for a length of not less than twenty ft. and the slide should be supported at regular intervals of 6ft using M.S. pipes support and the platform ladder with 25mm dia MS pipes with suitable hand rails and steps made out of G I sheet with tred 4" with powder coated finish, fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for t	Set	1	595000.00	615000.00	665000.00	655000.00	636000.00	700000.00	690000.00

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
12	Providing, fabricating and fixing of spiral climber of height not less than 10ft made out of 25mm dia MS pipe with Aluminium chequered plate platform of size 3'x3 ft with 4 legs made out of 75 mm dia G.I. Pipes fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be fitted with Single Lane slide made up of high quality FRP the slide is to fixed at a height of 9 ft and runs for a length of not less than 20 ft the slide should be supported at regular intervals of 4 ft using M.S. pipes support powder coated, fine quality FRP with .suitable design and as per drawing platforms should be placed at approximately 9 ft from ground level. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work.(All FRP items are gel water finish or stoving	Set	1	180000.00	200000.00	217000.00	210000.00	199000.00	225000.00	198000.00

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri.. C.M.Dayanidhi
3	Providing, fabricating and fixing play equipments consisting of the platform with 65mm dia MS pipe & Aluminium chequered plates of size 3'x3 ft fixed at 7 ft height from ground level with 4 legs made out of 75 mm dia G.I. Pipes fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof, the slide should be supported at regular intervals of 4 ft using M.S. pipes support powder coated, fine quality FRP with suitable design and as per drawing. The play equipment is to be fitted with Double seated swing for kids and Aqua bowl slide made up of high quality FRP the slide is to fixed at a height of 7 ft and runs for a length of not less than 12 ft. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work. (All FRP items are gel water finish or stoving paint	Set	1	220000.00	233000.00	240000.00	300000.00	270000.00	252000.00	260000.00

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
4	Providing, fabricating and fixing Special play equipments consisting of the platform with 65mm dia MS pipe & Aluminium chequered plates of size 3'x3 ft fixed at 5 ft height from ground level with 4 legs made out of 65 mm dia G.I. "B" Pipes fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be fitted with Monkey climber for kids and Roller slide(Moulded plastic rollers)fixed at a height of 5 ft and runs for a length of not less than 12 ft. the slide should be supported at regular intervals of 6 ft using M.S. pipes support powder coated, fine quality FRP with suitable design and as per drawing. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work. (All FRP items are gel water finish or stoving paint in ovens)	Set	1	180000.00	209000.00	217000.00	200000.00	220000.00	225000.00	230000.00

17

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
5	Providing, fabricating and fixing children play equipments consisting of the platform with 65mm dia MS pipe & Aluminium chequered plates of size 3'x3 ft & 3 ft height from ground level with 4 legs made out of 75 mm dia G.I. Pipes fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof, fine quality FRP with suitable design and as per drawing. The platform is to be fitted with Double twin wave slide for kids made up of high quality FRP material and also high quality plastic rope climber is to fixed at a height of 3 ft and runs for a length of not less than 5 ft. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work. (All FRP items are gel water finish or stoving paint in ovens)	Set	1	145000.00	154000.00	165000.00	160000.00	175000.00	165000.00	199000.00

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. G.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
6	Providing, fabricating and fixing Multiplay Special Slider Systems consisting of the platform with 25mm dia MS pipe & Aluminium chequered plates of size 3'x3 ft & 7 ft height from ground level with 4 legs made out of 65 mm dia G.I. Pipes fixed cement concrete 1:2:4. The platform is to be fitted with FRP Wave slide, spiral slide and standard slide with vertical ladder on one side each with G.I. sheet steps of tred 4" 25mm dia MS pipes with suitable hand rails fixed at a height of 5 ft and runs for a length of not less than 12 ft. The platforms are to be covered with pyramid shaped FRP roof, the slide should be supported at regular intervals of 4 ft using M.S. pipes support powder coated, fine quality FRP with suitable design and as per drawing. Moulded FRP slides are non-corrossive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work.	Set	1	520000.00	550000.00	535000.00	549000.00	577000.00	560000.00	585000.00

Sl No	Name of Work	Unit	Qty	Rates Quoted by Sri. B.S.Udaya Banu	Rates Quoted by Sri.C.N.S. Murthy	Rates Quoted by M/s Kiderplay Equipments	Rates Quoted by Sri. C.Rajshekar	Rates Quoted by M/s.SLR Enterprises	Rates Quoted by M/s Vinyaas Play Systems	Rates Quoted by Sri. C.M.Dayanidhi
7	Providing and fixing children play bridge with M.S, perforated tunnel, wave bridge, Arch bridge & hanging bridge made out of MS pipes and chequred plates uns for a height 11ft to 5ft. The work should be executed as per the standard specifications and directions of the engineer in charge of the with all lead and lift, loading and unloading and any incidental charges required for the successful completion of the work.(all swings chains are rubber coated & all 'S' hooks are stainless steel).	Set	1	120000.00	139000.00	155000.00	145000.00	190000.00	160000.00	175000.00

1 Rates quoted by Sri. B.S.Udaya Banu is the lowest amoung the three agency
2 Rates are reasonable when compared to market rates
3 Lowest rate quoted by Sri. B.S.Udaya Banu may be considered for approval

Assistant Engineer
(Horticulture - South Zone)

Horticulture Superintendent
South -Zone

ಗುತ್ತಿಗೆದಾರರ ಎಕ್ಕಿಕ ಕಡಿಮೆದರಗಳನ್ನು ನಮೂದಿಸಿರುವ
ಶ್ರೀ.ಬಿ.ಎಸ್. ಉದಯಬಾನುರವರು ದರಗಳನ್ನು ಕಾಮಗಾರಿಯ
ಅಂದಾಜು ಪತ್ರಿಕೆಯಲ್ಲಿ ಅಳವಡಿಸಲು ಮಾತ್ರ ಅನುಮೋದನೆ ಬಯಸಲಾಗಿದೆ.

14 ಮೈಸೂರು ಬೆಂಗಳೂರು